

New This Week

Sodding complete; final layer of asphalt scheduled.

Construction Area

Phase 1: Turnpike Rd, Radisson Rd
Phase 2: Lawn Terrace, Colonial Dr

2011 PAVEMENT MANAGEMENT PROGRAM ○ SEPT 30, 2011

Crews Finish Sodding, Schedule Final Layer Of Asphalt

In the past week, crews have completed the sodding and City crews have finished inspecting all sanitary sewers and storm sewers with video cameras to confirm that all the joints are sealed and no issues are present.

In the next week, the contractor will wrap up miscellaneous items, including some curb repairs.

The final layer of asphalt for the entire construction area is scheduled for the week of Oct 10. Homeowners will receive an orange construction notice the evening before work will occur in front of their home.

During the paving operation, no on-street parking will be allowed. Homeowners will still have access to their driveways, but temporary blockages of driveways and road section closures will occur. All the roads will be open to traffic by the end of the day.

For more information on the paving process, see "Paving Is A Four-Step Process" in the box at right. ○

Tips For Maintaining New Sod

Help maintain your new sod by following these simple guidelines:

- Sod requires about two inches of water per week until the roots take hold. Test for established roots by attempting to pull up an edge of the sod. If it pulls up easily, give it more time and continue watering at least two inches per week. If the sod edge does not come up, the roots have taken hold.
- Once the roots are established, water about one inch per week, which is the minimum amount needed to keep a lawn healthy and thriving.
- Don't mow new sod until the roots are established. Cut it first at the highest mower setting. The grass can then gradually be cut to the desired length. However, don't cut the grass to the desired length until next spring.
- Fertilizing should not be necessary until next spring

The contractor is responsible for maintaining the sod for the first 30 days after installation. The warranty primarily covers the sod if it fails to become established. If the sod was mowed too short (see tip above) or damaged by non construction activities, then it is not covered by the warranty. After that warranty period, the sod is the responsibility of the homeowner for watering and maintenance. ○



Paving Is A Four-Step Process

Laying down the final layer of asphalt is a four-step process.

- ① Trucks deliver asphalt mix at a temperature of at least 180° F and dump it into the paving unit. As the paver moves along the road, the asphalt is laid as a smooth mat.
- ② A steel drum roller compacts the fresh asphalt. A roller with tires then further compacts the entire layer of asphalt to achieve optimal density.
- ③ The steel drum roller makes a final pass to smooth the surface and provide some compaction in the upper layer of the asphalt (see photo above). Smooth roadway surfaces are intended to provide comfortable driving and improve water drainage.
- ④ The asphalt is allowed to cool and harden, which is important to minimize tracking, scuffing, or other surface marring. ○

Pre-Payment Of Special Assessments

If you are planning to pre-pay your assessment for the 2011 Pavement Management Program, please do so by **November 18, 2011**. If you pre-pay, the assessment will not be added to your property taxes in 2012.

To pre-pay your assessment, mail your check to City Hall at 7800 Golden Valley Rd, Golden Valley, MN 55427. You can also put your payment in the drop box near the front door of City Hall or pay in person at the General Services counter on the second floor. Also, please be aware that credit cards are not accepted.

The street assessments were approved by the City Council in spring 2011. If you have any questions about assessments and how they work, contact the Golden Valley Finance Department at 763-593-8009. ○

Reinstalling Irrigation And Fence Systems

To avoid spending tax dollars to relocate private irrigation and fence systems within City street right of way (ROW), homeowners are responsible for temporarily moving or relocating their own systems.

In areas behind the curb that have been graded smooth or have had sod laid, homeowners may reinstall irrigation and fence systems (eg, invisible fences) that were relocated before construction. For areas within the ROW, please have installation companies mark the reinstalled irrigation heads or invisible fences with locate flags. ○

SCHEDULES MAY CHANGE ON SHORT NOTICE Weather, delays by subcontractors, or other unforeseen events can cause schedule changes. The contractor makes an effort to notify residents as soon as possible.

CHECK DOORS FOR NOTICES The contractor will routinely notify you about upcoming work, particularly if the work will make your driveway inaccessible for most or part of a day (you will be able to get back into your driveway each evening). Please check all of the doors around your house for written notices of upcoming work.

CONSTRUCTION QUESTIONS At the construction site, please direct all project-related questions to City staff. For other questions, call Public Works at 763-593-8030. **If you would prefer to have Construction News emailed to you, contact Pat Schutrop at 763-593-3987 or pschutrop@goldenvalleymn.gov to get on the list.**

RECYCLING Recycling should be picked up as scheduled. Please continue to have your recycling curbside by 7 am on Fridays. The recycling contractor (Waste Management) will collect recycling in street reconstruction areas on schedule. Please continue to report all missed pick-ups to Waste Management at 952-890-1100. If you feel you are not getting optimum service, call the City's Public Works Department at 763-593-8030.

CONTACT US (When calling, please provide your address.)

City of Golden Valley

Mark Ray, Engineering Technician • 763-593-3960 • mray@goldenvalleymn.gov
Brian Dahlberg, Engineering Technician • 763-593-8112 • bdahlberg@goldenvalleymn.gov
Jeff Oliver, City Engineer • 763-593-8034 • joliver@goldenvalleymn.gov
Al Lundstrom, Park Maintenance Supervisor • 763-593-8046 • alundstrom@goldenvalleymn.gov
Jeannine Clancy, Director of Public Works • 763-593-8035 • jclancy@goldenvalleymn.gov

CenterPoint Energy

Customer Service Office • 612-321-5369

Special Needs?

The contractor will work with residents needing access for wheelchairs, Metro Mobility rides, etc. Call Public Works at 763-593-8030.

AFTER-HOUR EMERGENCIES

Call the Golden Valley Police Department at 763-593-8079 to report problems that require immediate assistance by the City (flooded street, disruption to water service, sanitary sewer back-up, etc). Your message will be relayed to on-call Public Works personnel.

PROJECT NEWSLETTERS

During construction, *Construction News* will be printed biweekly, or more frequently if needed. The newsletter will include updates on construction scheduling, phone numbers of contact persons, and other information that may be useful to you. **To get this newsletter by email, contact us at 763-593-3987 or pschutrop@goldenvalleymn.gov.**

TIPS & ANSWERS www.goldenvalleymn.gov/streets/pmp/

If you're wondering about various construction practices, or if you're looking for information about things like taking care of your new driveway or sod, go to the City website and check out the PMPs Tips & Answers page. If you don't find answers there, contact Public Works at 763-593-8030.

This document is available in alternate formats upon a 72-hour request. Please call 763-593-8006 (TTY: 763-593-3968) to make a request. Examples of alternate formats may include large print, electronic, Braille, audiocassette, etc.



7800 Golden Valley Road
Golden Valley, MN 55427-4588