


HDPE PLASTIC
ADJUSTMENT RINGS
(OR APPROVED EQUAL)

MIN. 2
OR AS DIRECTED BY
ENGINEER.
SEE NOTE:

SEAL ADJUSTMENT
RINGS (SEE NOTE)



PRECAST CONCRETE
BASE SLAB

OPENINGS AS
REQUIRED

NOTE:

CASTINGS SHALL BE NEENAH R3067-L WITH "L" TYPE GRATE.

IF MORE THAN 5 - 2" RINGS ARE NEEDED CONTRACTOR SHALL USE A COMBINATION OF 2", 6" AND 12" RINGS TO ACHIEVE NEEDED HEIGHT.

RINGS SHALL BE SEALED USING APPROVED FLEX-SEAL UTILITY SEALANT AND APPLICATION SHALL FOLLOW DETAIL GV-SS-010.

REINFORCING AND CONCRETE ARE TO BE IN ACCORDANCE WITH ASTM SPECIFICATION C478.

NOTE:

PLASTIC HDPE ADJUSTING RINGS (MIN. 2) USE A COMBINATION OF 2", 6" AND 12" RINGS TO ACHIEVE NEEDED HEIGHT. INCLUDE MIN. 2-2" RING IMMEDIATELY UNDER THE CASTING. RINGS SEALED W/BUTYL CAULK. SEE GV-SS-010

APPROVED JANUARY 1, 2018

CITY ENGINEER REG 23110

**CATCH BASIN
DESIGN K
WITH SUMP**

City of
Golden Valley

GV-ST-030